HPM SYSTEMS, INC.

February 22, 2026 Proposal: xxxxxx-rev#

First_Name Last_Name
Company
Address
City, State, Zip code

RE: Subject: xxxxxxxx
Site: xxxxxxxx

Dear First_Name,

Thank you for the opportunity to submit our proposal for assistance with the above referenced project. HPM Systems proposes to provide the equipment and services as outlined herein.

SCOPE OF WORK

I) DESIGN, PROJECT MANAGEMENT & CONTRACTOR COORDINATION

A) System design, block diagram, and matrix.
B) Coordinate installation, programming and testing with Client and installing contractors.

II) EQUIPMENT

A) Provide two (2) silane gas sensors.
B) Provide two (2) UV-IR flame sensors.
C) Provide two (2) exhaust pressure switches.
D) Provide two (2) horn/strobes
E) Provide one (1) EGO pull station.
F) Provide one (1) silane sensor for silane VMB.
G) Provide one (1) UV-IR flame sensor for silane VMB.
H) Provide one (1) silane sensor for Centura exhaust.
I) Provide one (1) ammonia sensor for Centura exhaust.
J) Provide one (1) nitrogen trifluoride sensor w/pyrolizer for Centura exhaust.
K) Provide one (1) nitrogen trifluoride sensor w/pyrolizer for abatement exhaust.
L) Provide two (2) exhaust pressure switches.

III) PLC & HMI PROGRAMMING, START-UP, TESTING & INSPECTIONS

A) Program PLC, HMI & touch screen for the above listed devices to provide gas detection alarm safety interlocks as per the approved control matrix.
B) Terminate cabling at the PLC.
C) Gas challenge and test sensors with controls contractor to verify programming.
D) Pre-inspection functional testing.
E) Demonstrate system for inspector at HazMat inspection.

IV) ELECTRICAL INSTALLATION

A) Subcontract electrician to install the above listed equipment and to run cables to seismic room and mezzanine remote PLC panels.
B) Terminate cabling at the above-mentioned devices, gas cabinets and PLC's.

<u>ASSUMPTIONS/EXCLUSIONS</u>

The scope of work is based on the following assumptions and/or exclusions:

A) Client shall be responsible for disabling the active alarms during the field services, calibration and functional testing on any part of the gas detection system. HPM Systems shall not be responsible for shutdowns, site interruptions, or other loss of production.
B) Fire alarm system changes, wiring, programming or permitting are excluded.
C) Current PLC programs and Wonderware programs shall be made available to HPM Systems.
D) Current building CAD plans shall be provided to HPM Systems.
E) Panel drawings changes or updates are excluded. We do not have CAD files for your panels.
F) Permitting and permit fees are excluded. If separate permits are required because the HPM design drawings are not submitted along with the tool installation permit plana, HPM Systems will submit a change order for the permit/plan check fees and permitting labor after the permit has been issued.

G) Work shall be performed during regular business hours. Overtime is excluded.

H) The proposed fee does not include any services or parts to correct deficiencies that may be found during the project with regards to sensor placement, parts, hardware or wiring, however, HPM Systems can assist in correcting those deficiencies under a separate contract.

I) Please note that the distributed gas detection system PLCs are near maximum capacity. We will need to have cabling for new devices and controls pulled to each panel to fulfill the monitoring requirements for this project. Please note that future gas detection projects may require the installation of an additional PLC panel.

J) Any additional equipment and services not specifically mentioned in this quote are excluded.

PROFESSIONAL FEE

I)	**DESIGN, PROJECT MANAGEMENT & CONTRACTOR COORDINATION**	**$12,960**
II)	**EQUIPMENT**	**$47,805**
III)	**PLC & HMI PROGRAMMING START-UP, TESTING & INSPECTIONS**	**$25,600**
IV)	**ELECTRICAL INSTALLATION**	**$71,875**
TOTAL FEE		**$158,320**

We look forward to working with you on this project. Please contact us at (408) 615-6900 or 408-391-2934 or via email at dstevenson@hpmsystems.com for questions.

Sincerely,

Don Stevenson
Principal Project Manager
HPM Systems, Inc.
CA contractor license # 810246

Client
Authorized Representative

Signature Date

P.O.# (if applicable)

Cc: Bert Buehler, President

HPM SYSTEMS RATE SCHEDULE

The following fee schedule applies through December 31, 2026

PROFESSIONAL FEES

Project Assistant:	$125
Office Manager / Administrator:	$135
Automation / Field Technician:	$145
Associate Automation Designer / Integrator:	$145
Automation Designer / Integrator:	$165
Associate Engineer / Programmer:	$165
Automation Engineer / Programmer, Filed Service Manager:	$185
Senior Automation Designer / Technician / Integrator:	$195
Senior Automation Engineer / Programmer / Project Manager:	$215
Principal, Project Manager:	$225
Principal, Professional Engineer:	$245
Chemical Specialist:	$275

Subcontractors & Equipment ..... Cost +15-25%

Special Charges:

- All after-hours, weekends, and emergency services requested by clients will be provided at 1.5 times the standard labor rate. All holiday services will be provided at 2.0 times the standard labor rates.
- Expert witness testimony, depositions and similar meetings associated with pending or on-going legal actions shall be provided at 1.5 times the standard labor rate.
- All credit card transactions will include 5% of the total charge added to the price.
- A 4-hour minimum labor charge applies to all unscheduled maintenance and emergency services.
- Swing shift work shall be labor rates above +10%. Graveyard shifts shall be rates above +20%.
- Prices on equipment are subject to change due to tariffs.

Calibration Gas	$25 for each hour of field usage
Service Van	$25 for each hour of field usage or a maximum of $100 per day

REIMBURSABLE EXPENSES

Direct Expenses ..... Cost Plus 15-25% Mark-up
Including: permit fees, mail & courier services, leased equipment, reproductions, travel and other direct expenses.

Mileage (other than Service Van) ..... $0.70 /Mile

Plotting and Reproductions (In-House)

Black & White Plots	$7 per sheet
Color Plots	$15 per sheet
Scan	$7 per sheet
Color Prints	$1 per sheet